


DRAFT TENDER SCHEDULE


Issued to :

Original / Duplicate
Item No.Name of the Work: Construction of Ranga Mandhira Building in Ward No. 10 (Doddaballapur)
Vidyaranyapura Sub Division.


Sl. No.	Quantity.	Description	Unit	Rates	
				In Figures	
1	130.00	Earth work excavation for foundation of buildings, culverts water supply, sanitary line and electrical conduits either in pits or in trenches 1.5m and above in width, in Hard soil not exceeding 1.5m, in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50m, after breaking of clods etc complete as per specifications and directions of engineer in charge of the work	Cum	223.66	
2	98.85	Providing and laying in position plain cement concrete of mix M 7.5 with OPC cement at 180kgs, with 40mm and down size graded granite metal coarse aggregates @0.892cum and fine aggregates @0.57cum machine mixed, concrete laid in layers not, exceeding 15cms, thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing etc complete as per specifications and directions of engineer in charge of the work	Cum	4211.38	
3	43.20	Providing and constructing granite / trap / basalt size stone masonry in basement with cement mortar 1:6, edges of stones chistle dressed in courses not less than 15 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing with new stones etc complete as per specifications and directions of engineer in charge of the work	Cum	5208.84	
4	24.30	Providing and laying in position plain cement concrete of mix M 15 with OPC cement @ 240kgs, with 20mm and down size graded granite metal coarse aggregates @0.878cum and fine aggregates @0.459cum machine mixed, concrete laid in layers not, exceeding 15cms, thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing etc complete as per specifications and directions of engineer in charge of the work	Cum	4690.50	
5	288.00	Providing flush pointing to square rubble, course or uncoursed stone masonry with cement mortar 1:3, 20 mm deep, after raking joints to depth of 20mm nicely lining, including cost of materials, labour, curing etc complete as per specifications and directions of engineer in charge of the work	Sqm	78.44	
6	4.91	Providing and laying cement concrete using 20mm and down size granite coarse aggregates and fine aggregates of ready mixed concrete for R.C.C works laid in 15cms thick layers and well compacted including vibrating curing etc., including smooth finish in CM 1:3, with all lead and lift etc., complete. (exclusive of cost of steel and fabrication charges) Ready mixed cement concrete for Beams, column, Staircase and Roof with M-20(cement -320 Kg/Cum) etc complete as per specifications and directions of engineer in charge of the work	Cum	6348.34	

Sl. No.	Quantity.	Description	Unit	Rates	
				In Figures	
7	5.40	Providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost pf materials, labour, HOM of machinery complete as per specifications. Specification No. KBS 4.6.3 -do- for TMT Bars Fe 415 etc complete as per specifications and directions of engineer in charge of the work	qtl	7244.04	
8	158.40	Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for columns , pillars, piers, post and struts, circular or curved in plan including cost of all materials, labour etc complete as per specifications and directions of engineer in charge of the work	sqm	836.34	
9	196.00	Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for sides and soffits of beams , beam haunchings, cantilever girders, bressumers and lintels not exceeding 1 m in depth including cost of all materials, labour etc complete as per specifications and directions of engineer in charge of the work	sqm	239.56	
10	546.00	Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for stairs (excluding landing) except spiral staircase including cost of all materials, labour etc complete as per specifications and directions of engineer in charge of the work	sqm	460.04	
11	3100.00	Fabricating supplying and erecting M.S. TubulerTruss of span upto 10m bottom and top member is provided with 50x50x6mm double equale angles, welded back to back and in between top and bottom line, in ereas of mid section is provided with 50x50x6mm equal single angle for vertical and inclined members and at supporting ends 40x40x5mm single angle is provided all the members are weldeded togeher with 6mm gusset plate as per drawing, Nos CBS/SD/K- mantap/9/MND/97. The enter truss is anchored in RCC column buy using 4Nos of M.S anchor bolts at each support, with 10mm thick base plate and shoe plate. The work includes cutting, straightening , pacing in position of M.S angle and welding wherever necessary, and applying one of red oxide primer coat to all the members including cost of all materials, labour charges,and higher charges of mechneries for cutting welding, granding and erection equipments, etc complete as per specifications and directions of engineer in charge of the work	kgs	125.08	
	225.00	Providing Meta color sheet roofing with J or L hooks, bolts and nuts 8mm dia C.I plain and bitumen washers over the existing ~~purlins, rafters and trusses~~ includeing cost of materials, labour, etc complete as per specifications and ~~directions of engineer in~~ charge of the work	sqm	1200.00	


Signature of the Contractor


Executive Engir
Byatarayanapura D
BBMP, Bangalor

ಕರಡು ಬೆಂಡರ್ ಪಡ್ಕೂರನ್ನು
ಬಿಡ್ಡುಪಡೆಗನ ಸಂಖ್ಯೆ..... 1012
ಬಿಡ್ಡುಪಡಿ ಮಾಡಿ/ಇಲ್ಲದೆ
ಅನುಮೋದನೆ ನೀಡಿರಾಗಿದೆ


Superintending Engineer
Yelahanka Zone
BBMP, Bangalore-52